



ADDENDUM #2 Rumney School Project:

1. Subbase material identified in detail C/LA300 and E/LA300 shall be Crushed Gravel, VAOT Spec #**704.05**
2. Filled areas, particularly along the existing roadway and the swale island feature – shall be compacted in order to prevent slumping. Fill material shall be placed in loose lifts not exceeding (8) inches. Each lift shall be thoroughly compacted and shall be obtained satisfactory density prior to proceeding with the next lift. Fill areas shall be compacted to 92% of Standard Maximum Density. Testing will be at the discretion of the owner and paid for by the owner.