



Rumney School Stormwater Project Addendum 7-27-16

- Bid Specification, Section 02231, 2.01 D: Add. Orange Snow/Safety Fencing (48” Ht) may be used for tree protection. This substitution also applies to Detail B/LA302. All other tree protection requirements remain per the contract documents.
- Bid Specification, Section 02920, 1.4: withdrawn. A licensed Surveyor or Civil Engineer is not required for stake out. Electronic CAD files are available for contractor use upon request and/or additional dimensional layout information will be provided by the Landscape Architect.
- Bid Specification, Section 02772, 1.04.A: replaced. Handle boulders to prevent chipping, scarring and staining to the extent practicable, recognizing that boulders will be transported via dump truck and placed using an excavator bucket. Boulders with cracks and/or breakage will be rejected. This notation also applies to Detail B/LA300; replacing Note #2.

In addition, we are providing the following clarifications on the woody debris: we are open to reducing the DBA size to 12” min; the **branches and bark** SHALL be stripped and removed; we are open to hardwood species, as well as hemlock or cedar.

In addition, a request was made for a source for the black locust timber. Shelburne Farms (<http://www.shelburnefarms.org/about/farm-products/woodlands>; dbishop@shelburnefarms.org) has had black locust lumber available recently. Another source is “A Black Locust Connection” located in Colrain, MA.